

# TASK 450 square direct

suspended

059-2211037K



Project / Type

Notes

Count / Date



### General

Ceiling , Suspended

white , RAL9010 <sup>1</sup>

IP20

1880 lm

### LED

3000 K

CRI ≥ 90

L90 / 50000 h

photobio. safety RG 0 - no Risk

initial MacAdam ≤ 3 SDCM

R<sub>g</sub>: 96 , R<sub>r</sub>: 90 , R<sub>t(1-15)</sub>: 90

MR 0.61

MDER 0.56

### Optical

Microprismatic

UGR < 19 , ≥65° <3000 cd/m²

PstLM ≤ 1.0 <sup>2</sup>

SVM ≤ 0.4 <sup>2</sup>

### Electrical

DALI-2

15.0 W

PC1 220-240V

125 lm/W

1 DALI Addr.

### Physical

1 cable 1500 mm

length 450 mm


width 450 mm

height 41 mm


4 kg

<sup>1</sup> RAL code <sup>2</sup> Value of containing product at full load (undimmed)

### Light distribution



### Product drawing



### Installation instructions



### Lighting calculator

